



RADON TEST CONDUCTED BY:

CMH Home Inspections, llc

Craig Howard Lic #HI3833 Radon Technician Lic #R2239

Cheri Howard Radon Technician Lic #R2643

510 North Ride, Tallahassee, FL 32303

850-567-2603 choward@CMHHomeInspections.com

RADON TEST PROCEDURES

- Keep windows and doors to the exterior closed, except for entering and exiting, for at least 12 hours prior to the beginning of the test.
- Keep windows and doors to the exterior closed, except for entering and exiting, during the test period.
- Heating and air-conditioning system fans that re-circulate air should be set to "auto".
- Do not operate fans or other machines which bring in air from outside.
- Do not create drafts near test device.
- Small exhaust fans operating only for short periods of time may run during the test.
- Fans that are part of a radon-reduction system should be run during the test.
- Do not tamper with or move testing devices.